

James M. Fischer Larry W. Dority

#### Attorneys at Law Regulatory & Governmental Consultants

101 Madison, Suite 400 Jefferson City, MO 65101 Telephone: (573) 636-6758 Fax: (573) 636-0383

July 31, 2001

Dale Hardy Roberts Secretary/Chief Regulatory Law Judge Missouri Public Service Commission P.O. Box 360 Jefferson City, Missouri 65102

FILED2 Service Commission

Greeley Gas Company, Case No. GR-2001-36

Dear Mr. Roberts:

Pursuant to the Commission's Order Establishing ACA Balance And Closing Case issued on July 3, 2001, in the above-referenced matter, enclosed for filing are the original and eight (8) copies of the Greeley Gas Company Reliability Study-Missouri. A copy of the Reliability Study has been hand-delivered or mailed this date to parties of record.

Thank you for your attention to this matter.

Sincerely,

Jene M. Fischer

**Enclosures** 

cc:

Office of the Public Counsel

Dana K. Joyce

FILED<sup>2</sup>

JUL 3 1 2001

Service Commission

Greeley Gas Company Reliability Study Missouri

## Contents

•	Peak Day Projection - Three Years (Since the Heat Load Factors were larger by utilizing Jan & Feb only, these were used in the Peak Day Projections)	Page 1-3
•	Calculation of Base Load Factors	Page 4
•	Calculation of Heat Load Factors using Jan-Feb only	Page 5
•	Calculation of Heat Load Factors using Nov-Feb	Page 6
•	Base Load and Heat Load Factor Table using Jan-Feb only	Page 7
•	Base Load and Heat Load Factor Table using Nov-Feb	Page 8
•	Customer growth statistics	Page 9
•	Actual vs. Projected comparison	Page 10-18
•	Market Area Reserve Margin Calculation	Page 19
•	Penalty vs. Pipeline Capacity cost	Page 20
	Considerations to cover capacity deficit	Page 21

# **Traditional Methodogy**

Peak Day De William	Projected Factors					
Mean Temperature F	10	5	0	-5	-10	
Degree Days	55	60	65	70	75	
Residential Customers	14,175					
Baseload Heating Load Total	855 10,603 11,458	855 11,567 12,422	855 12,531 13,385	855 13,495 14,349	855 14,459 15,313	0.0603 0.0136
Commercial Customers	1,051					
Baseload Heating Load Total	233 2,491 2,724	233 2,718 2,951	233 2,944 3,177	233 3,171 3,404	233 3,397 3,630	0.2215 0.0431
Public Authority	204					
Baseload Heating Load Total	40 1,034 1,074	40 1,129 1,168	40 1,223 1,262	40 1,317 1,356	1,41,1 1,450	0.1947 0.0922
Industrial	50	50	50	50	÷ _ 50	
Lost & Unaccounted For	260	280	300	320	340	
Total Requirements	15,566	16,870	18,175	19,479	20,784	
Total Requirements - MMBtu	15,815	17,140	18,466	19,791	21,116	

Mcf converted using 1.016 Lost & Uaccounted For = 2%

٠.,

Subscribed Capacity	18,234	18,234	18,234	18,234	18,234
Flowing Capacity	9,389	9,389	9,389	9,389	9,389

# **Traditional Methodogy**

Peak Day Design - Market Area (Year 2) Williams Natural Gas System Units in Mcf						
Mean Temperature F	10	5	0	-5	-10	
Degree Days	55	60	65	70	75	
Residential Customers	14,459					
Baseload Heating Load Total	836 10,497 11,333	836 11,452 12,287	836 12,406 13,242	836 13,360 14,196	836 14,314 15,150	0.0578 0.0132
Commercial Customers	1,051					
Baseload Heating Load Total	226 2,653 2,879	226 2,894 3,120	226 3,136 3,362	226 3,377 3,603	226 3,618 3,844	0.2149 0.0459
Public Authority	204			~~		
Baseload Heating Load	35 957	35 1,044	35 1,131	35 1,218	35 1,305	0.1724 0.0853
Total Industrial	992 50	1,079 50	1,166,50	1,25 <u>3</u> 50	1,340 50	
Lost & Unaccounted For	260	280	50 300	320	340	
Total Requirements	15,514	16,817	18,119	19,422	20,724	
Total Requirements - MMBt	15,763	17,086	18,409	19,733	21,056	

Mcf converted using 1.016 Lost & Uaccounted For = 2%

 Subscribed Capacity
 18,234
 18,234
 18,234
 18,234
 18,234
 18,234

 Flowing Capacity
 9,389
 9,389
 9,389
 9,389
 9,389

# Traditional Methodogy

Peak Day Design - Market Area (Year 3) Williams Natural Gas System Units in Mcf						Projected Factors
Mean Temperature F	10	5	0	-5	-10	
Degree Days	55	60	65	70	75	
Residential Customers	14,748					
Baseload Heating Load Total	816 10,464 11,279	816 11,415 12,231	816 12,366 13,182	816 13,317 14,133	816 14,269 15,084	0.0553 0.0129
Commercial Customers	1,051					
Baseload Heating Load Total	219 2,815 3,034	219 3,071 3,290	219 3,327 3,546	219 3,583 3,802	219 3,839 4,058	0.2084 0.0487
Public Authority	204			•		
Baseload Heating Load Total	31 879 909	31 958 989	31 1,038 1,069 (1	31 1,118 1,149	31 1,198 1,229	0.1501 0.0783
Industrial	50	50	50	50	50	
Lost & Unaccounted For	260	280	300	320	340	
Total Requirements	15,533	16,840	18,147	19,454	20,761	
Total Requirements - MMBt	15,781	17,109	18,437	19,765	21,093	
Mcf converted using 1.016 Lost & Uaccounted For = 2%						
Subscribed Capacity Flowing Capacity	18,234 9,389	18,234 9,389	18,234 9,389	18,234 9,389	18,234 9,389	

### Based on 2000 Data

### Calculation of Baseload Factor for Peak Day Design - Market Area

A - From Sheet 4 (Actual Consumption from Banner E-Volume Reports)

•	Actual			Normalized			
_	July	August	September	July	August	September	Total
Residentail	24550	20380	24431	24550	20380	24431	69361
Commercial	8071	5454	7256	8071	5454	7256	20781
Public Authorit	1155	1037	1355	1155	1037	1355	3547

B - From Sheet 4 (Number of Customers from Banner E-Volume Reports)

	July	August	September	July	August	September	Avg
Residential	13547	13542	13537	13547	13542	13537	13542.0
Commercial	1017	1003	1009	1017	1003	1009	1009.7
Public Authorit	205	206	204	205	206	204	205.0

#### Average Consumption per Customer

			Average
		Average	Baseload
	Baseload	No. of	Consumption
	Consumption	Customer	Per Customer
Residential	69361	13542.0	5.12
Commercial	20781	1009.7	20.58
Public Authorit	3547	205.0	17.30

### Average Consumption per Customer Divided by the Total Number of Days

	Consumption Per Customer	No. of Days	Baseload Factor
Residential	5.12	91	0.0563
Commercial	20.58	91	0.2262
Public Authority	17.30	91	0.1901

### Based on 2001 Data

### Calculation of Heat Load Factor for Peak Day Design - Market Area

### A. From sheet 4 ( Actual Consumption from Banner E-Volumes Report)

	Mcf	Mcf	Customers (	Customers
	January	February	January	February
Residentail	295,579	223,529	13,896	13,917
Commercial	75,195	50,258	1,059	1,054
Public Authority	27,973	21,641	204	204

Minus:

**Baseload Consumption (See Baseload Factor Calculation)** 

	Mcf	Mcf	Customers	Customers
	January	February	January	February
Residential	24,253	21,939	13,896	13,917
Commercial	7,426	6,676	1,059	1,054
Public Authority	1,202	1,086	204	204

Equals:

**Heat Sensitive Consumption (HSC)** 

(Total Consumption minus Baseload Consumption)

	Mcf	Mcf	Total	
	January	February	Mcf	Customers
Residential	271,326	201,590	472,917	13,869
Commercial	67,769	43,582	111,351	1,043
Public Authority	26,771	20,555	47,326	204

#### B. Heat Load Per Customer Divided by Actual Degree Days = Heat Load Factor(HLF)

	January	February	Peak Month Factor
Cycle HDD =	1366	1097	2,463
Residential	0.0143	0.0133	0.0138
Commercial	0.0476	0.0381	0.0433
Public Authority	0.0961	0.0919	0.0942

Note:

Cycle Heating Degree Days are adjusted from Calender Heating Degree Days in the following manner: January - 12/15 thru 01/14; February - 01/15 thru 02/14

### Based on 2001 Data

## Calculation of Heat Load Factor for Peak Day Design - Market Area

### A. From sheet 4 ( Actual Consumption from Banner E-Volumes Report)

	Mcf	Mcf	Mcf	Mcf	Customers Customers Customers	Customers
	November	December	January	February _	November December January	February
Residentail	82,579	213,666	295,579	223,529	13,785 13,878 13,896	13,917
Commercial	14,778	42,037	75,195	50,258	1,020 1,038 1,059	1,054
Public Authority	6,859	20,731	27,973	21,641	203 204 204	204

Minus :	Baseload C	onsumption	n ( See Ba	aseload Facto	r Calculation)
	Mof	Mof	Mof	Mof	Custo

	Mcf	Mcf	Mcf	Mcf	Customers Customers Customers
	November	December	January	February	November December January February
Residential	23,283	24,221	24,253	21,939	13,785 13,878 13,896 13,917
Commercial	6,922	7,279	7,426	6,676	1,020 1,038 1,059 1,054
Public Authority	1,158	1,202	1,202	1,086	203 204 204 204

Equals:

**Heat Sensitive Consumption (HSC)** 

(Total Consumption minus Baseload Consumption)

	Mcf	Mcf	Mcf	Mcf	Total	Average No. of
	November	December	January	February	Mcf	Customers
Residential	59,296	189,445	271,326	201,590	721,657	13,869
Commercial	7,856	34,758	67,769	43,582	153,966	1,043
Public Authority	5,701	19,529	26,771	20,555	72,556	204

### B. Heat Load Per Customer Divided by Actual Degree Days = Heat Load Factor(HLF)

	November	December	January	February	Peak Mon Factor
Cycle HDD =	396	1021	1366	1097	3,88
Residential	0.0108	0.0134	0.0143	0.0133	0.013
Commercial	0.0190	0.0326	0.0476	0.0381	0.038
Public Authority	0.0707	0.0939	0.0962	0.0920	0.09

#### Note:

<sup>1)</sup> Baseload Factor baseload months during 2001. baseload months during 2001.

<sup>2)</sup> Cycle Heating Degree Days are adjusted from Calender Heating Degree Days in the following manner: January - 12/15 thru 01/14; February - 01/15 thru 02/14

# **Greeley Gas Company Baseload and Heatload Consumption Factors**

### **BASELOAD FACTORS**

			_	
M	arı	(At	フヘ	ne

			ING! III	JE EUITE			
		Residential		Commercial	Public	Pub. Auth.	
Year	Residential	Delta	Commercial	Delta	Authority	Delta	Industrial
1995	0.0689		0.2590				2.8855
1996	0.0655	-0.0034	0.2713	0.0123			0.9670
1997	0.0620	-0.0035	0.2113	-0.0600			0.8571
1998	0.0651	0.0031	0.1924	-0.0189	0.2485		
1999	0.0594	-0.0057	0.2080	0.0156	0.2124	-0.0361	
2000	0.0563	-0.0031	0.2262	0.0182	0.1901	-0.0223	
2001							
2002							
2003							
Projected Fa	ctors						
Average Delt	a	-0.0025		-0.0066		-0.0223	
Year 1	0.0603		0.2215		0.1947		
Year 2	0.0578		0.2149		0.1724		
Year 3	0.0553		0.2084		0.1501		

### **HEATLOAD FACTORS**

Market Zone

		Residential		Commercial	Public	Pub. Auth.	
Year	Residential	Delta	Commercial	Delta	Authority	Delta	Industrial
1999	0.0145		0.0377		0.1081		
2000	0.0135	-0.0010	0.0398	0.0021	0.0952	-0.0129	
2001	0.0138	0.0003	0.0433	0.0035	0.0942	-0.0010	
2002							
2003							
Projected Fa	ctors						
Average Delt	a	-0.0004		0.0028		-0.0070	
Year 1	0.0136		0.0431		0.0922		
Year 2	0.0132		0.0459		0.0853		
Year 3	0.0129		0.0487		0.0783		

Year 1 = Average of the factors over the last three years Year 2 & 3 = Average plus the average Delta

# Greeley Gas Company Baseload and Heatload Consumption Factors

### **BASELOAD FACTORS**

Market Zone Residential Commercial Public Pub. Auth. Year Residential Delta Commercial Delta Authority Delta Industrial 2.8855 1995 0.2590 0.0689 0.9670 1996 0.0655 -0.0034 0.2713 0.0123 1997 0.0620 -0.0035 0.2113 -0.0600 0.8571 0.0031 0.1924 0.2485 0.0651 -0.0189 1998 1999 0.0594 -0.0057 0.2080 0.0156 0.2124 -0.0361 2000 0.0563 -0.0031 0.2262 0.0182 0.1901 -0.0223 2001 2002 2003 Projected Factors Average Delta -0.0025 -0.0066 -0.0223 0.0603 0.2215 0.1947 Year 1 Year 2 0.0578 0.2149 0.1724 Year 3 0.0553 0.2084 0.1501

### **HEATLOAD FACTORS (Includes November and December in calculations)**

	Market Zone							
Residential Commercial Public Pub. Auth.								
Year	Residential	Delta	Commercial	Delta	Authority	Delta	Industrial	
2001	0.0134	0.0000	0.0381	0.0000	0.0918	0.0000		
2002								
2003								
Projected F	actors							
Average De	elta	0.0000		0.0000		0.0000		
Year 1	0.0134		0.0381		0.0918			
Year 2	0.0134		0.0381		0.0918			
Year 3	0.0134		0.0381		0.0918			

Greeley Gas Company WNG Peak Day Study Winter Growth Statistics For the Months of December, January, and February

### Williams Central Pipeline System - Total Market

### **RESIDENTIAL CUSTOMERS**

	Average		Annual	Expected Annual	Expected Number of
Year	Customers	Delta	Growth Percent	Growth	Customers
1995					
1996	12,232				
1997	12,491	259	2.00%		
1998	12,726	235	2.00%		
1999	13,275	549	4.00%		
2000	13,603	328	2.00%		
2001	13,897	294	2.00%		
Expected Gr	owth - Year 1		2.00%	278	14,175
Expected Gr	owth - Year 2		2.00%	284	14,459
Expected Gr	owth - Year 3		2.00%	289	14,748

### **COMMERCIAL CUSTOMERS**

	Average		Annual	Expected Annual	Expected Number of
Year	Customers	Delta	Growth Percent	Growth	Customers
1995					
1996	1,151		1		
1997	1,539	388	25.00%		
1998	1,176	-363	-31.00%		
1999	1,039	-137	-13.00%		
2000	1,049	10	1.00%		
2001	1,051	2	0.00%		
Expected Gr	owth - Year 1		0.00%	0	1,051
Expected Gr	owth - Year 2		0.00%	0	1,051
Expected Gr	owth - Year 3		0.00%	0	1,051

### **PUBLIC AURTHORITY CUSTOMERS**

	Average		Annual	Expected Annual	Expected Number of
Year	Customers	Delta	Growth Percent	Growth	Customers
1995					
1996	0				
1997	0	0	0.00%		
91998 1999	0	0	#DIV/0!		
<sup>17</sup> 1999	204	204	100.00%		
2000	205	1	0.00%		
2001	204	-1	0.00%		
Expected Gr	owth - Year 1		0.00%	0	204
Expected Gr	owth - Year 2		0.00%	0	204
Expected Gr	owth - Year 3		0.00%	0	204

# Greeley Gas Company Summary of Tests Results Comparison of Peak Day Model to Actual Peak Day Requirements

GR-01-394; Data Request No. 45

Schedule B-1

Test Number	1	2	3	4	5	6	7	8
Actual Heating Degree Days	41	57	53	60	57	45	58	33
Day of the Week	Monday	Monday	Monday	Monday	Tuesday	Thursday	Friday	Thursday
Date	November 20, 2000	December 11, 2000	December 18, 2000	January 1, 2001	January 2, 2001	February 1, 2001	February 9, 2001	March 1, 2001
Actual Day Comparison				•				
(1) Calculation w/ Est. Factors	11,817	16,102	15,056	16,964	16,080	12,961	16,361	9,820
(2) Actual	<u>7,986</u>	<u>16,488</u>	<u>14,419</u>	<u>13,348</u>	<u>12,493</u>	<u>11,799</u>	<u>13,052</u>	<u>8,379</u>
Variance Volume	-3,831	386	-637	-3,616	-3,587	-1,162	-3,309	-1,441
Variance Percent	-32.4%	2.4%	-4.2%	-21.3%	-22.3%	-9.0%	-20.2%	-14.7%

Selection Criteria = the peak days from the two shoulder months (November & March); two peak days from the remaining winter months.

<sup>(1)</sup> Result of projected peak day baseload and heatload factors from model times actual heating degree days times actual number of customers.

<sup>(2)</sup> Actual pipeline deliveries less third party transportation.

	Day	

	i cot bu			
Peak Day Design - Marke Williams Natural Gas Sys Units in Mcf	,	Actual Factors 2000	Projected Factors	Projected Load
Actual Mean Temperature F	24			
Actual Degree Days November 20, 2000	41			
Residential Customers	13,785			
Baseload Heating Load Total	776 7,573 8,350	0.0563 0.0134	0.0603 0.0136	831 7,687 8,518
Commercial Customers	1,020			
Baseload Heating Load Total	231 1,656 1,887	0.2262 0.0396	0.2215 0.0431	226 1,802 2,028
Public Authority	203			
Baseload Heating Load Total	39 787 826	0.1901 0.0946	0.1947 0.0922	40 767 807
Industrial	50			50
Customer Requirements	11,112			11,403
Lost & Unaccounted For	222			228
Total Requirements	11,334		•	11,631
Total Requirements - MMBtu Mcf converted using 1.016 Lost & Uaccounted For = 2%	11,516			11,817
WNG Deliveries Less: Transportation Greeley Deliveries	8,370 <u>384</u> 7,986			8,370 <u>384</u> 7,986
(Over)/Under Estimated Percent	-3,530 -30.7%			-3,831 -32.4%

Test	Day	#	2
100		17	-

Peak Day Design - Marke Williams Natural Gas Sy Units in Mcf		Actual Factors 2000	Projected Projected Factors Load
Actual Mean Temperature F	7		
Actual Degree Days December 11, 2000	57		
Residential Customers	13,878		
Baseload Heating Load Total	781 10,600 11,381	0.0563 0.0134	0.0603 837 0.0136 10,758 11,595
Commercial Customers	1,038		
Baseload Heating Load Total	235 2,343 2,578	0.2262 0.0396	0.2215 230 0.0431 2,550 2,780
Public Authority	204		
Baseload Heating Load Total	39 1,100 1,139	0.1901 0.0946	0.1947 40 0.0922 1,072 1,112
Industrial	50		50
Customer Requirements	15,148		15,537
Lost & Unaccounted For	303		311
Total Requirements	15,451		15,848
Total Requirements - MMBtu Mcf converted using 1.016 Lost & Uaccounted For = 2%	15,698		16,102
WNG Deliveries	17,124		17,124
Less: Transportation Greeley Deliveries	<u>636</u> 16,488		<u>636</u> 16,488
(Over)/Under Estimated Percent	790 5.0%		386 2.4%

Te	st	Day	#	3

Peak Day Design - Marke Williams Natural Gas Sy Units in Mcf		Actual Factors 2000	Projected Projected Factors Load
Actual Mean Temperature F	12		
Actual Degree Days December 18, 2000	53		
Residential Customers	13,878		
Baseload Heating Load Total	781 9,856 10,637	0.0563 0.0134	0.0603 837 0.0136 10,003 10,840
Commercial Customers	1,038		
Baseload Heating Load Total	235 2,179 2,413	0.2262 0.0396	0.2215 230 0.0431 2,371 2,601
Public Authority	204		
Baseload Heating Load Total	39 1,023 1,062	0.1901 0.0946	0.1947 40 0.0922 997 1,037
Industrial	50		50
Customer Requirements	14,162		14,528
Lost & Unaccounted For	283		291
Total Requirements	14,445		14,819
Total Requirements - MMBtu Mcf converted using 1.016 Lost & Uaccounted For = 2%	14,677		15,056
WNG Deliveries	15,055		15,055
Less: Transportation Greeley Deliveries	<u>636</u> 14,419		<u>636</u> 14,419
(Over)/Under Estimated Percent	-258 -1.8%		-637 -4.2%

Test	Day	#	4
------	-----	---	---

Peak Day Design - Marl Williams Natural Gas S Units in Mcf		Actual Factors 2001	Projected P Factors	Projected Load
Actual Mean Temperature F	5			
Actual Degree Days January 1, 2001	60			
Residential Customers	13,896			
Baseload Heating Load Total	782 13,757 14,539	0.0563 0.0165	0.0603 0.0136	838 11,339 12,177
Commercial Customers	1,059			
Baseload Heating Load Total	240 3,285 3,525	0.2262 0.0517	0.2215 0.0431	235 2,739 2,974
Public Authority	204			
Baseload Heating Load Total	39 1,376 1,415	0.1901 0.1124	0.1947 0.0922	40 1,129 1,169
Industrial	50		-	50
Customer Requirements	19,529			16,370
Lost & Unaccounted For	391			327
Total Requirements	19,920		_	16,697
Total Requirements - MMBtu Mcf converted using 1.016 Lost & Uaccounted For = 2%	20,238			16,964
WNG Deliveries	14,003			14,003
Less: Transportation Greeley Deliveries	<u>655</u> 13,348			<u>655</u> 13,348
(Over)/Under Estimated Percent	-6,890 -34.0%			-3,616 -21.3%

Test	Day	#	5
------	-----	---	---

·	rest Day	# 5		
Peak Day Design - Mark Williams Natural Gas Sy Units in Mcf		Actual Factors 2001	Projected Factors	Projected Load
Actual Mean Temperature F	8			
Actual Degree Days January 2, 2001	57			
Residential Customers	13,896			
Baseload Heating Load Total	782 13,069 13,852	0.0563 0.0165	0.0603 0.0136	838 10,772 11,610
Commercial Customers	1,059			
Baseload Heating Load Total	240 3,121 3,360	0.2262 0.0517	0.2215 0.0431	235 2,602 2,837
Public Authority	204			
Baseload Heating Load Total	39 1,307 1,346	0.1901 0.1124	0.1947 0.0922	40 1,072 1,112
Industrial	50			50
Customer Requirements	18,608			15,609
Lost & Unaccounted For	372			312
Total Requirements	18,980			15,921
Total Requirements - MMBtu Mcf converted using 1.010 Lost & Uaccounted For = 2%	19,169			16,080
WNG Deliveries Less: Transportation Greeley Deliveries	13,148 <u>655</u> 12,493			13,148 <u>655</u> 12,493
(Over)/Under Estimated Percent	-6,676 -34.8%			-3,587 -22.3%

Test Day # 6					
Peak Day Design - Market Area Actual Projected Projected					
Williams Natural Gas Sys		Factors 2001	Factors	Projected Load	
Actual Mean Temperature F	20				
Actual Degree Days February 1, 2001	45				
Residential Customers	13,917				
Baseload Heating Load Total	784 10,333 11,117	0.0563 0.0165	0.0603 0.0136	839 8,517 9,356	
Commercial Customers	1,054				
Baseload Heating Load Total	238 2,452 2,691	0.2262 0.0517	0.2215 0.0431	233 2,044 2,277	
Public Authority	204				
Baseload Heating Load Total	39 1,032 1,071	0.1901 0.1124	0.1947 0.0922	40 846 886	
Industrial	50			50	
Customer Requirements	14,928			12,569	
Lost & Unaccounted For	299			251	
Total Requirements	15,227			12,820	
Total Requirements - MMBtu Mcf converted using 1.011 Lost & Uaccounted For = 2%	15,395			12,961	
WNG Deliveries Less: Transportation Greeley Deliveries	12,334 <u>535</u> 11,799			12,334 <u>535</u> 11,799	
(Over)/Under Estimated Percent	-3,596 -23.4%			-1,162 -9.0%	

Test Day # 7					
Peak Day Design - Mark Williams Natural Gas Sy Units in Mcf		Actual Factors 2001	Projected Projected Factors Load		
Actual Mean Temperature F	7				
Actual Degree Days February 9, 2001	<b>58</b>				
Residential Customers	13,917				
Baseload Heating Load Total	784 13,319 14,102	0.0563 0.0165	0.0603 839 0.0136 10,978 11,817		
Commercial Customers	1,054				
Baseload Heating Load Total	238 3,161 3,399	0.2262 0.0517	0.2215 233 0.0431 2,635 2,868		
Public Authority	204				
Baseload Heating Load Total	39 1,330 1,369	0.1901 0.1124	0.1947 40 0.0922 1,091 1,131		
Industrial	50		50		
Customer Requirements	18,920		15,866		
Lost & Unaccounted For	378		317		
Total Requirements	19,298		16,183		
Total Requirements - MMBtu Mcf converted using 1.011 Lost & Uaccounted For = 2%	19,510		16,361		
WNG Deliveries Less: Transportation Greeley Deliveries	13,587 <u>535</u> 13,052		13,587 <u>535</u> 13,052		
(Over)/Under Estimated Percent	-6,458 -33.1%		-3,309 -20.2%		

Test	Day	#8	
------	-----	----	--

Peak Day Design - Marke Williams Natural Gas Sys Units in Mcf		Actual Factors 2001	Projected Factors	Projected Load
Actual Mean Temperature F	31			
Actual Degree Days March 1, 2001	33			
Residential Customers	13,907			
Baseload Heating Load Total	783 7,572 8,355	0.0563 0.0165	0.0603 0.0136	839 6,241 7,080
Commercial Customers	1,054			
Baseload Heating Load Total	238 1,798 2,037	0.2262 0.0517	0.2215 0.0431	233 1,499 1,732
Public Authority	204			
Baseload Heating Load Total	39 757 795	0.1901 0.1124	0.1947 0.0922	40 621 661
Industrial	50			50
Customer Requirements	11,237			9,523
Lost & Unaccounted For	225			190
Total Requirements	11,462		-	9,713
	ï			
Total Requirements - MMBtu Mcf converted using 1.011 Lost & Uaccounted For = 2%	11,589			9,820
WNG Deliveries	8,755			8,755
Less: Transportation Greeley Deliveries	<u>376</u> 8,379			<u>376</u> 8,379
(Over)/Under Estimated Percent	-3,210 -27.7%			-1,441 -14.7%

GR-01-0394

### Greeley Gas Company Reserve Margin Calculation Schedule C

Peak Day Design ( -10 Mean Temp. & 75 HDD).

	ACA			·
	Peak Day	Forecasted Peak Day		Day
	12/11/00	Year 1	Year 2	Year 3
Residential	11,943	15,313	15,150	15,084
Commercial	2,704	3,630	3,844	4,058
Public Authority	1,193	1,450	1,340	1,229
Industrial	<u>64</u>	<u>50</u>	<u>50</u>	<u>50</u>
Requirements	15,903	20,443	20,384	20,421
Lost & Unaccounted	<u>325</u>	<u>340</u>	<u>340</u>	<u>340</u>
Total Customers Requirements	16,228	20,783	20,724	20,761
Btu Factor	1.016	1.016	1.016	1.016
Peak Day Requirements	16,488	21,116	21,056	21,093
	T.			
Subscribed Capacity	•			
TA-0544	15,055	15,055	15,055	15,055
TA -0546	529	529	529	529
TA -0891	<u>2,650</u>	<u>2,650</u>	<u>2,650</u>	<u>2,650</u>
Greeley Deliveries	18,234	18,234	18,234	18,234
Reserve Margin	1,746	-2,882	-2,822	-2,859

### Notes:

<sup>1.</sup> The 16,488 units in MMBtu represent the maximum deliveries net of estimated daily endusers off Williams Central Pipeline.

# Greeley Gas Company Williams Central Pipeline Transportation Analysis of Penalty vs Additional Capacity

Missouri Case No. GR-01-394

				Annual De	mand Fees
	Penalty	Penalty	Penalty	Full	Market
Exceeds MDQ	Quantity	Price	Amount	Path	Only
	(a)	:		(b)	©
Up to 3%	540	\$0.00	\$0		
Between 3% and 10%	1,260	\$25.00	\$31,500		
Over 10%	<u>1,200</u>	\$50.00	\$60,00 <u>0</u>		
	3,000	•	\$91,500	\$302,875	\$100,850

- (a) Rounded capacity deficit shown on Data Request No. 21.
- (b) Full Path is the combined capacity in both the production and market areas.
- © Market area capacity only.

### Williams Penalty Gas Tariff

Under Deliveries of between 3% and 10% are the greater of \$10 or 5 times the gas daily price. Under Deliveries of greater than 10% are the greater of \$20 or 10 times the gas daily price.

Williams Demand Charges
Deficit Quantity (Dth) 3000
Production Demand Rate \$5.6118
Market Demand Rate \$2.8014

### Assumption:

(1) Gas Daily for Williams Natural Gas Midpoint is estimated at \$5.00.

# Greeley Gas Company Anticipated Steps to Remedy Capacity Deficit

Greeley would attempt to cover any anticipated shortfall above the maximum contract quantities to meet its system requirements by contracting another party's firm transportation capacity bundled with the gas commodity (city gate deliveries). Additionally, Greeley is exploring a number of other options to address the peak day capacity deficit in the Williams Central Pipeline market area. These options include; securing additional capacity on Williams in both the production and market areas or securing additional capacity in the market area coupled with a commodity peaking service delivered to the market area. Greeley has contacted representatives of Williams Central Pipeline to discuss the availability of additional capacity and delivery points on the pipeline.