

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

INDEX

Sheet No.

- 1 Index
- 2 Map of Service Area
- 5 Legal Description of Service Area
- 8 Schedule of Rates
- 9 Schedule of Service Charges

Sheet
Number

Rule
Number

Rule
Subject

- 10. 1 Definitions
- 16 2 General Matters
- 17 3 Limited Authority of Company Employees
- 18..... 4 Applications for Sewer Service
- 21 5 Inside Piping and Customer Service Sewer
- 25 5A Pressure Collecting Sewers
- 28 6 Improper or Excessive Use
- 30 7 Discontinuance of Service
- 36 8 Termination of Service
- 37 9 Interruptions in Service
- 38 10 Bills for Service
- 42 11 Extension of Collecting Sewers

- * Indicates new rate or text
- + Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

Reserved for future use

* Indicates new rate or text
+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year


ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

Map of Service Area



* Indicates new rate or text
+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year


ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

Map of Service Areas – Oakbrook and Johnson Ridge



* Indicates new rate or text
+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year


ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

Map of Service Areas – Johnson Ridge and Eastern Estates



- * Indicates new rate or text
- + Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

LEGAL DESCRIPTION OF SERVICE AREA – PLATTE COUNTY

Area 1

In Township 53N, Range 34W, in Platte County, Missouri: The East 1440 feet of Section 20 lying South of the Platte River; the West½ of Section 21 lying South of the Platte River and the East ½ of Section 21 lying South of Interurban Road, except those properties owned by the Missouri Department of Conservation; all of Section 30 lying South of HH Highway, except any property within the Platte City corporate limits; all of Section 29 lying South and East of HH Highway; all of Section 28, except any property North and West of HH Highway; the Southwest Quarter of the Southwest Quarter of Section 27; all of Section 31 lying North and East of Platte City corporate limits; all of Section 32 lying North and East of Platte City corporate limits; all of Section 33 except those properties in the RedRock Subdivision; and the west 1400 feet of Section 34, except those properties in the Clemstone Subdivision.

In Township 52N, Range 34W, in Platte County, Missouri: all of Section 5 and Section 6, except those properties within the Kansas City corporate limits and those areas South of Interstate Highway 435; and all of section 4 North of Highway 92, except those properties within the Kansas City corporate limits.

Area 2

Generally an area South of Platte City and West of interstate Highway 435, in Platte County, Missouri, more particularly described as Follows:

All of the following property in Township 52N, Range 34W: all of the South¾ of Section 6, located South of Interstate Highway 29 and West of interstate Highway 435; all of Section 7, located West of interstate Highway 435; and all of Sections 18 and 19, located West of Interstate Highway 435; and

All of the following property located in Township 52N, Range 35W: all of the East½ of the Southeast 1/4 of Section 1, all of Sections 11, 12, 13, and 24, and all of Sections 14 and 23, lying east of the Platte River.

* Indicates new rate or text

+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

LEGAL DESCRIPTION OF CLAY COUNTY SERVICE AREA – OAKBROOK

All of a tract of land generally south of 136th Street described as follows: The West½ of the East ½ of Section 7, Township 52 North, Range 31 West, Clay County, Missouri, Except an area described as Lot 1, Popejoy Acres, a subdivision in Clay County, Missouri.

Beginning at the Northeast corner of SW¼ in Section 7, Township 52 North, Range 31 West in the Clay County, thence Southerly, along the East line of said Quarter Section, a distance of 1315.71 feet to the Southeast corner of said Quarter Section; thence Westerly along the South line of North½ of the Southwest¼ to a point, a distance of 422.71 feet; thence North 00 degrees, to a point, a distance of 32.50 feet; thence North 66 degrees West, to a point, a distance of 184.30 feet; thence North 43 degrees West, to a point, a distance of 670.04 feet; thence South 59 degrees West, to a point, a distance of 524.7 feet; thence North 00 degrees, to a point, a distance of 264.90 feet; thence North 89 degrees West, to a point, a distance of 823.50 feet; thence North 00 degrees, to a point, a distance of 656.05 feet; thence South 89 degrees East, a distance of 2268.85 feet more or less to the Point of Beginning. Said tract of land contains 45.2 acres (1,968,912 square feet) more or less.

A tract of land located in the East Half of the Northeast Quarter of Section 7, Township 52 North, Range 31 West, in Clay County, Missouri, being more particularly described as follows:

Commencing at the Northwest corner of said Northeast Quarter; thence North 89°48'13" East along the North line of said Northeast Quarter, 1,321.92 feet to the Northwest corner of the East Half of said Northeast Quarter, said point also being the Point of Beginning; thence North 89°48'13" East, continuing along said North line, 512.00 feet; thence South 00°33'02" East, 1,447.00 feet; thence South 89°48'13" West, 512.00 feet to a point on the West line of said East Half; thence North 00°33'02" West, along said West line, 1,447.00 feet to the Point of Beginning.

Contains 740,850 square feet, or 17.01 acres, m/1.

- * Indicates new rate or text
- + Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

**LEGAL DESCRIPTION OF CLAY COUNTY SERVICE AREA - JOHNSON
RIDGE**

All of a tract of land generally North of NE 132nd Street and West of North Eastern Road in Township 52 North, Range 32 West, Clay County, Missouri, described as follows: The East $\frac{1}{2}$ of the Southwest $\frac{1}{4}$ of Section 4; the South $\frac{1}{2}$ of the Northwest $\frac{1}{4}$ of the Southeast $\frac{1}{4}$ of Section 4; The South $\frac{1}{2}$ of the Southeast $\frac{1}{4}$ of Section 4; the East $\frac{1}{2}$ of the Northwest $\frac{1}{4}$ of Section 9; and all of the Northeast $\frac{1}{4}$ of Section 9, except Lots 6, 7, 8, and 9 of Burton Estates, a subdivision in Clay County, Missouri.

**LEGAL DESCRIPTION OF CLAY COUNTY SERVICE AREA - EASTERN
ESTATES**

A tract of land in part of Section 9, Township 52 North, Range 32 West, Clay County, Missouri and being more particularly described as follows:

Commencing at the Southeast Comer of the Northeast Quarter of Section 9, Township 52 North, Range 32 West; Thence N00°23'09"E, Along the East Line of said Northeast Quarter, a distance of 40.00 feet; Thence N89°46'47"W, along a Line 40.00 feet North of and Parallel with the South line of said Northeast Quarter, a Distance of 40.00 feet to the point of beginning on the Southeast Comer; Thence N89°46'47"W, Along the South line of property, a Distance of 1141.32 feet to the Southwest Comer of property; Thence N00°23'56"E, along the West line of property, a Distance of 1290.76 feet to the Northwest Comer of property; Thence S89°31'34"E, along the North line of said property, a Distance of 1141.02 feet to the Northeast Comer of property; Thence S00°23'09"W, along the East line of said property, a Distance of 1285.71 feet to the point of beginning; Containing 33.75 Acres, More or Less.

- * Indicates new rate or text
- + Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

Schedule of Rates

RESIDENTIAL RATE:

Sewer Service Monthly Rate (Clay and Platte Counties) \$ 50.13

COMMERCIAL RATES:

Facility	Monthly Rate
----------	--------------

Fox Creek	\$ 70.19
-----------	----------

Running Horse	\$ 70.19
---------------	----------

Townhomes of Oak Valley	\$ 200.53
-------------------------	-----------

Seven Bridges	\$ 325.86
---------------	-----------

Shiloh Springs	\$ 501.33
----------------	-----------

Grinder Pump Fee \$6.02/month
(Applicable to those customers with a grinder pump)

TAXES: These rates do not include any municipal, state or federal taxes computed on either billing or consumption basis. Any such taxes applicable shall be added as separate items in rendering each bill.

* Indicates new rate or text

+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

Schedule of Service Charges

One time fees associated with activities not included in monthly rates:

Late Charges

Billings will be made and distributed at monthly intervals. Bills will be rendered net, bearing the last date on which payment will then be considered delinquent. The period after which the payment is considered delinquent is 21 days after rendition of the bill, unless that date falls upon a Sunday, legal holiday, or any other day when the offices of Timber Creek that are regularly used for the payment of customer bills are not open to the general public, in which case the day on which payment is considered delinquent shall be extended through the next business day. A charge of 3% times the unpaid balance or \$5, whichever is highest, will be added to delinquent amounts each month. If a customer has not been late in the previous twelve months, the Company may at its discretion waive the late fee. After disconnection for non-payment, additional delinquent charges will not be assessed if the only new charge on the prior month's bill was the assessment of the delinquent charge.

Returned Check Charge

A returned check charge of up to \$25.00 per check will be due on all checks returned from the bank for insufficient funds.

Automated Clearing House (ACH) NSF

A charge of up to \$25.00 per ACH transaction will be collected for ACH transactions reversed due to insufficient funds.

Disconnection / Reconnection

The charge for reconnection after service disconnection by the Company for violation of Rule 7 herein shall be the total actual cost of disconnection and reconnection of water service by the water utility provider plus a one-time \$10 fee.

Permit/Connection Inspection Fee

A fee of \$100.00 will be charged for permit and inspection of a new service connection to the collecting sewer or new sewer extension connection to Company owned collecting sewer.

* Indicates new rate or text

+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

Connection Re-Inspection Fee

A fee of \$50.00 will be charged for any re-inspection of the new service connection that is not the fault of the Company.

Rule 1 – Definitions

- A. An "APPLICANT" is a person, firm, corporation, governmental body, or other entity that has applied for sewer service and/or an extension of collecting sewers along with additional plant facilities; two or more such entities may make one application for a sewer extension and be considered one APPLICANT. An "ORIGINAL APPLICANT" is an APPLICANT who entered into any contract or agreement with the Company for an extension of collecting sewers and/or additional plant facilities, contributed funds or utility plant assets to the Company under the terms of the contract or agreement, and is eligible for refunds under the terms of the contract or agreement as additional Applicants connect to such extensions or plant facilities.
- B. "B.O.D" denotes Biochemical Oxygen Demand. It is the quantity of oxygen utilized in the biochemical oxidation of waste matter under standard laboratory conditions expressed in milligrams per liter.
- C. CLASS 1 COMMERCIAL BUILDING" shall mean any structure, buildings, portion of a building or combinations of buildings in the same compound utilized, or to be utilized, by a retail or service business which, on the premises, does not: 1) manufacture any items or products; or 2) prepare and/or serve any types of food products; or 3) provide washing facilities for motor vehicles; or 4) service or repair motor vehicles; or 5) provide overnight accommodations for travelers.
- D. CLASS 2 COMMERCIAL BUILDING" shall mean any structure, building or portion a building or combinations of buildings in the same compound utilized, or to be utilized, by a retail or service business which, on the premises: 1) prepares

* Indicates new rate or text

+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

- and/or serves any types of food products; or 2) provides washing facilities for motor vehicles; or 3) services or repairs motor vehicles; or 4) provides overnight accommodations for travelers.
- E. CLASS 1 INDUSTRIAL BUILDING" shall mean any structure, building, portion of a building or combinations of buildings in the same compound utilized, or to be utilized, by a single entity whose primary use is for the manufacture, fabrication, processing, storage and/or assembly of any product.
- F. A "COLLECTING SEWER" is a pipeline, including force pipelines, gravity sewers, interceptors, laterals, trunk sewers, manholes, lampholes, and necessary appurtenances, including service tees, wyes and saddles, which is owned and maintained by the Company, located on public property or on private easements, and used to transport sewage waste from the Customer's service connection to the point of disposal. A "PRESSURE COLLECTING SEWER" is a collecting sewer pipeline, including tees, wyes, and saddles, operated under pressure from pump units owned and operated by customers connected to the pipeline, and is sometimes referred to generically as a COLLECTING SEWER.
- G. The "COMPANY" is Timber Creek Sewer Company, acting through its officers, managers, or other duly authorized employees or agents.
- H. A "CUSTOMER" is any person, firm, corporation or governmental body which has contracted with the Company for sewer service, or is receiving service from the Company, or whose facilities are connected for utilizing such service, and except for a guarantor is responsible for payment for service.
- I. The "DATE OF CONNECTION" shall be the date the permit for a service connection is issued by the Company. In the event no permit is taken, and a service connection is made, the date of connection shall be determined based on available information, such as construction/occupancy permits, or water or electric service turn-on dates, or maybe the date of commencement of construction of the building

- * Indicates new rate or text
+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

upon the property.

- J. A "DEVELOPER" is any person, firm, corporation, partnership or any entity that, directly or indirectly, holds title to, or sells or leases, or offers to sell or lease, or advertises for sale or lease, any lots in a subdivision.
- K. "DISCONTINUANCE OF SERVICE" is intentional cessation of the use of sewer service by action of the Company not at the request of the Customer. Such DISCONTINUANCE OF SERVICE may be accomplished by methods including physical disconnection of the service sewer, or turn-off of water service by the water utility at the request of the Company.
- L. "DOMESTIC SEWAGE" is sewage, excluding storm and surface water, resulting from normal household activities; and, "NON-DOMESTIC SEWAGE" is all sewage other than DOMESTIC SEWAGE including, but not limited to, commercial or industrial wastes. See Rule 6 - Improper or Excessive Use.
- M. A "FOUNDATION DRAIN" is a pipe installed inside or outside the foundation of a structure for the purpose of draining ground or subsurface water away from the foundation.
- N. "pH" is the relative degree of acidity or alkalinity of water as indicated by the hydrogen ion concentration. pH is indicated on a scale reading from 1-14, with 7.0 being neutral, below 7.0 acid, and above 7.0 alkaline; more technically defined as the logarithm of the reciprocal of the hydrogen ion concentration.
- O. A "PUMP UNIT" is a self-contained facility consisting generally of a tank and an electric pump and may include liquid level controls, an alarm, and check valves; the Pump Unit may either separate solid from liquid waste retaining the solid waste in the tank and pumping the liquid waste under pressure to collecting sewer pipelines (septic tank effluent pump or STEP), or may pump waste water including solids to a collecting

* Indicates new rate or text

+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

sewer or a pressure collecting sewer (grinder pump). The PUMP UNIT is installed, owned and maintained by the Customer.

P. A "RETURNED CHECK" is a check that is returned to the Company from any bank unpaid for any reason.

Q. A "SADDLE" is a fitting that connects the Customer's Service Sewer to the collecting sewer whether it be a gravity collecting sewer or a pressure collecting sewer; the saddle clamps around the collecting sewer pipeline into which pipeline a hole is cut, and the Service Sewer is connected to the Saddle thereby connecting it to the collecting sewer.

R. A "SERVICE CONNECTION" is the connection of a service sewer to the Company's collecting sewer either at the bell of a tee branch or wye branch, or the bell of a saddle placed on the barrel of the collecting sewer.

S. A "SERVICE SEWER" or "CUSTOMER'S SERVICE SEWER" is a pipe with appurtenances installed, owned and maintained by the Customer, used to conduct sewage from the Customer's premises to the collecting sewer, excluding service tees, wyes or saddles. For Customers connected to a pressure collecting sewer and utilizing a pump unit, the portion of the Service Sewer between the pump unit and the collecting sewer is a pressurized portion of the Service Sewer. In addition to other parts and fittings this shall include a stop cock accessible to the Company for turn-off of sewage flow and a check valve to prevent backflow of wastewater under pressure in the pressure collecting sewer. The SERVICE SEWER is constructed, owned and maintained by the Customer.

T. SEWER USAGE FACTOR (SUF) or Water Use Factor (WUF), a multiplier used to estimate the volume of incoming water that returns to the sewer system in other than single family residential settings. Where usage information is available, WUF will be equal to the amount calculated for a single-family residence

* Indicates new rate or text

+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

multiplied by a water usage factor. The WUF shall be determined by dividing the average monthly usage in gallons by 7,000 gallons but shall not be less than 1. The minimum factor is one. Where usage information is not readily available, the WUF shall be determined by the application of the standard equivalent dwelling unit (EDU) attributable to the use of the premises. The minimum unit for each classification of users is one. The number of EDUs attributable to each type of use or user will be calculated in accordance with the Summary of Equivalent Dwelling Units, a copy of which is included in the tariff. The Company will attempt to get the usage information from the water provider or request bill copies from the customer to establish future sewer bills based on actual use. The present methodology for calculation of special contract rates will be reevaluated as part of the next rate case.

- U. A "SUBDIVISION" is any land in the state of Missouri which is divided or proposed to be divided into two or more lots or other divisions of land, whether contiguous or not, or uniform in size or not, for the purpose of sale or lease, and includes re-subdivision thereof.
- V. "SUSPENDED SOLIDS" are the insoluble materials suspended or dispersed in wastewater, expressed in milligrams per liter on a dry weight basis, as determined by standard procedures.
- W. A "TEE" is a three-way one-piece pipe fitting in the shape of the letter "T" that is a part of the Collecting Sewer pipeline and to which the Customer's Service Sewer is connected.
- X. "TERMINATION OF SERVICE" is the cessation of the use of sewer service requested by the Customer. Such TERMINATION OF SERVICE shall be accomplished by a method verified and recognized by the Company, and may include physical disconnection of the service sewer, termination or disconnection

- * Indicates new rate or text
+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

of water service by the water utility, or the Company's observation of non-occupancy of the unit served.

- Y. The word "UNIT" or "LIVING UNIT" shall be used herein to define the premises or property of a single sewer user, whether or not that sewer user is the Customer. It shall pertain to any building whether multi-tenant or single occupancy, residential or commercial, owned or leased. Each mobile home in a mobile home park, and each rental unit of a multi-tenant rental property are considered as separate Units for each single family or firm occupying same as a residence or place of business.
- Z. A "WYE" or "WYE BRANCH" or "Y" or "Y BRANCH" is a three-way one-piece pipe fitting in the shape of the letter "y" that is a part of the collecting sewer pipeline, and to which the Customer's service sewer is connected.

- * Indicates new rate or text
+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

Rule 2 - General Matters

- A. Every applicant, upon signing an application for sewer service or any Customer accepting service rendered by the Company, shall be considered to have expressed consent to be bound by these Rates, Rules and Regulations.
- B. The Company's Rules and Regulations governing rendering of service are set forth in the numbered sheets of this tariff. The rates applicable to appropriate class of service in particular service areas are set forth in rate schedules and constitute a part of this tariff.
- C. The Company reserves the right, subject to approval from the Missouri Public Service Commission, to prescribe additional Rates, Rules or Regulations or to alter existing Rates, Rules or Regulations as it may from time-to-time deem necessary or proper.
- D. After the effective date of these rules, all new facilities, construction contracts and written agreements shall conform to these Rules and Regulations, in accordance with the statutes of the State of Missouri, and the Rules and Regulations of the Missouri Public Service Commission. Pre-existing facilities that do not conform with these Rules and Regulations may remain, if said facilities do not cause any service problems or improper use, and reconstruction is impractical.
- E. The point of sewer service provided by the Company shall be at the service connection.
- F. The Company shall have the right to enter the Customer's premises, after reasonable notice, for the purposes of inspection to ensure compliance with these Rules and Regulations. Company personnel shall identify themselves and make these inspections only at reasonable hours.

* Indicates new rate or text

+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

Rule 3 – Limited Authority Of Company Employees

- A. Employees or agents of the Company are expressly forbidden to demand or accept any compensation for any service rendered to its Customers except as covered in the Company's Rules and Regulations.
- B. No employee or agent of the Company shall have the right or authority to bind it by any promise, agreement or representation contrary to the letter or intent of these Rules and Regulations.
- C. The Company shall not be responsible for damages due to any failure to remove wastewater from the premises, or for interruption if such failure or interruption is without willful default or negligence on its part.
- D. The Company shall not be liable for damages because of any interruption of sewer service, or for damages caused by defective piping, fittings, fixtures or appliances on the Customer's premises and not owned by the Company.
- E. The Company shall not be liable for damages due to damages from Acts of God, civil disturbances, war, government actions, and other uncontrollable occurrences.

* Indicates new rate or text
+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

Rule 4 – Applications For Sewer Service

- A. A written application for service, signed by the Customer, and accompanied by the appropriate fees as provided in the Schedule of Rates, the Schedule of Service Charges, Rule 11 - Extension of Collecting Sewers, and other information required by these Rules, must be received from each Customer. Said application must be filed in writing three (3) business days in advance stating the street, house number, name of the applicant, name of the property owner, and the time, at which connection is to be made.
- B. The Company shall have the right to refuse service for failure to comply with the rules herein, or if the Customer owes a past due bill not in dispute for sewer service at any location within the Company's service area.
- C. In any case where a collecting sewer extension or unusual construction or equipment expense is necessary to furnish the service, the Company may require a contract for service specifying a reasonable period of time for the Company to provide the service.
- D. If the Customer is a tenant, the Company shall notify the owner of the property or owner's property manager or other agent, if known to the Company, that such owner or property manager may be responsible for payment of the sewer service bill associated with the application.
- E. A prospective Commercial or Industrial Customer shall, upon request of the Company, present in writing to the Company a list of devices that will discharge to the collecting sewers, the amount and specifications of any discharge, and the location of any buildings. The Company will then advise the Customer of the form and the character of the wastewater collection facilities available. If a sewer extension as provided for in Rule 11 - Extension of Collecting Sewers will be necessary, or if the Customer will be required to own, operate, and maintain a pretreatment facility, the Customer will also be so advised.

- * Indicates new rate or text
- + Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

- F. When sewer charges are based on water usage, the Company reserves the right to refuse sewer service to any applicant unless said applicant agrees to install a water meter accessible by the Company, so that there will be a basis for sewer charges. The Company and Customer may agree to an estimated water use amount, on an interim basis for a period not to exceed six (6) months, to allow time to install suitable metering equipment.
- G. The Company will determine or approve the location of the service connection. Service sewers will not be extended along public streets or roadways or through property of others in connecting with collecting sewers. If a service connection is requested at a point not already served by a collecting sewer of adequate capacity, the collecting sewer shall be extended in accordance with Rule 11 - Extension of Collecting Sewers, unless in the Company's judgment such a collecting sewer would serve no other future purpose and a service sewer may be constructed to serve the Customer's premises in a reasonable manner.
- H. A new service connection shall be authorized when all conditions in the above paragraphs, and Rule 5 – Inside Piping and Customer Service Sewer, regarding application, construction and inspection provisions, are met.
- I. No substantial addition to the water using equipment or appliances connected to the sewer system shall be made by Commercial or Industrial Customers except upon written notice to and with the written consent of the Company.
- J. When a service sewer is to be connected to the collecting sewer, the plumber employed by the customer shall obtain the connecting accessories from the company. The plumber shall advise the company 24 hours in advance of when he expects to make the connection so a representative of the company can inspect the installation. The company must inspect any connection made by the customer prior to trench backfilling. The applicant or the applicant's plumbing contractor shall comply with the latest trench safety requirements required by OSHA. The trench shall be adequately braced or sloped back in

* Indicates new rate or text

+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

accordance with OSHA requirements. A commercial quality ladder shall be provided so that the company's inspector can safely access the bottom of the trench excavation. If the trench has caved-in before the inspection by the company, the excess material shall be removed to allow proper inspection of the sewer installation.

- * Indicates new rate or text
- + Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

Rule 5 – Inside Piping And Customer Service Sewer

- A. The Customer is obligated to construct, repair, and maintain the service sewer from the collecting sewer to the building, and make the connection to the collecting sewer, with the approval of the Company. The Customer shall notify the Company prior to cleaning or repairing the service sewer.
- B. Construction of the service sewer, and connection to the collecting sewer shall be subject to the inspection and approval of the company. No backfill shall be placed until the work has been inspected by the company. In the event the customer or the customer's agent shall damage a wye branch or saddle, or cause damage to the cost collecting sewer, then the customer shall be responsible for the cost to repair any such damage, including replacement of pipe or appurtenance as necessary.
- C. Plumbing specifications of all governmental agencies having jurisdiction, and these Rules and Regulations, in effect at the time of connection, must be met. The Company may deny service or may discontinue service where foundation drains, downspouts, or other sources of surface or storm water are permitted to enter the sewer system through either the inside piping or through the building sewer.
- D. A separate and independent service sewer shall generally be required for every building. Exceptions are:
 - 1. When one building stands at the rear of another building on an interior lot where a proper service sewer cannot be constructed through an adjoining easement. In that situation, the service sewer from the front building may be extended to the rear building and it will be considered as one service sewer.

* Indicates new rate or text

+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

2. When two or more buildings are a part of a complex that cannot be subdivided.
- E. The gravity service sewer shall be constructed using ductile iron pipe, polyvinyl chloride pipe (PVC), ASTM specification or equal; or other suitable material approved by the Company. Only those jointing materials and methods that are approved by the Company may be used. Joints shall be tight and waterproof. Any part of the service sewer that is located within ten (10) feet of a water main or water service pipe shall be constructed of ductile iron or PVC pressure pipe. The pipe shall be bedded according to the manufacturer's specifications and on undisturbed earth or fill compacted to at least ninety-five percent (95%) proctor density. Fill may be non-organic soil or aggregate.
- F. The size and slope of the gravity service sewer shall be subject to the approval of the Company, but in no event shall the diameter be less than four (4) inches. The slope of such four (4) inch gravity sewer pipe shall not be less than one-eighth (1/8) inch per foot.
- G. Whenever possible, the service sewer shall be brought to the building at an elevation below the basement floor. No building sewer shall be laid parallel to or within three (3) feet of any bearing wall except where the service sewer enters the building area. The depth shall be sufficient to afford protection from frost. The service sewer shall be laid at a uniform grade and in straight alignment insofar as possible. Changes in direction shall be made only with properly curved pipes and fittings. A ninety (90) degree bend in the service sewer shall be accomplished by using two (2) forty-five (45) degree bends with a straight section of pipe between the 45 degree bends. A cleanout may be added every 100 feet for service purposes.
- H. Existing service sewers may be used in connection with new buildings only when they are found on examination and test to meet all requirements of the Company.

* Indicates new rate or text
+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

- I. In any building in which a building drain is too low to permit the required slope of the service sewer, sanitary sewage carried by such drain shall be lifted by approved artificial means and discharged to the service sewer. No water operated sewage ejector shall be used.
- J. All excavations required for the installation of a service sewer and connection to the collecting sewer shall be open trench work unless otherwise approved by the Company. Pipe laying and backfill shall be performed in accordance with the latest published engineering specifications of the manufacturer of the materials used, and all applicable local plumbing codes.
- K. The connection of the service sewer to the collecting sewer shall be made at the tee branch or wye branch, if such branch is available at a suitable location. If the collecting sewer is vitrified clay pipe of twelve-inch (12") diameter or less and there is no properly located tee branch or wye branch at a suitable location, such a branch shall be furnished and installed by the Customer at a location specified by the Company and by an installation method approved by the Company. If the collecting sewer is greater than twelve inches (12") in diameter, or is PVC of any size, a neat hole may be cut at a location specified by the Company, and a saddle shall be furnished installed by the Customer to which the service sewer will be connected. The invert of the service sewer at the point of connection shall be at the centerline or higher elevation of the collecting sewer. The connection shall be secure and watertight. The wye branch, tee branch, or saddle shall become a part of the Company's collecting sewer and owned by the Company after installation.
- L. Any change in the location of an existing service connection and/or service sewer requested by the Customer shall be made at the Customer's expense.
- M. Company personnel may not work on piping or facilities not owned by the Company, unless authorized by the Customer.

* Indicates new rate or text

+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

- N. Customer Service Sewers may not be extended along public streets or roadways or through property of others in connecting with the Company's collecting sewers. The service sewer may, however, extend through the collecting sewer easement and roadway easement as necessary in order to be connected to a collecting sewer located across and adjacent to a street in front of the Customer's living unit. The service sewer must be laid in a straight line and at right angles to the collecting sewer and the face of the structure or as nearly so as possible. Any deviation from this because of physical obstruction will be at the discretion of the Company.

- * Indicates new rate or text
+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

Rule 5A – Pressure Collecting Sewers

- A. This rule applies to customers on a pressurized collection system and is not applicable to customers on a gravity collection system. All rules not specifically applicable to gravity flow sewers and services are also applicable.
- B. The company will provide a written application for prospective customers to use to request sewer service, with the application specifying when a pump station is necessary including information regarding a current estimate for the cost to establish service to a specific lot. Installation costs of the pump unit, pump station, control panel, electrical service and the service sewers between the dwelling and the company's collecting sewers are the responsibility of the customer, the developer or the builder. Electricity costs for pump operation shall be the responsibility of the customer.
- C. The company will ensure that collecting sewers, whether gravity or pressure sewers, are available to each platted lot in the subject subdivisions, with such collecting sewers to be installed at the developers' cost.
- D. The company will establish specifications for the construction of the customers service sewers and pump stations and procedures for connection of the service sewers to its collecting sewers, including the location of the point of connection of the service sewers to the collecting sewers, and will provide such specifications and procedures to the subdivision developers, known builders and service applicants.
- E. The Company will conduct an inspection of the customers' service sewer from the building to the Company's collecting sewers and the customers' pump station installation prior to the ditch being filled in to ensure that these facilities are constructed in accordance with its specifications and will maintain records of all such inspections.

* Indicates new rate or text

+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

- F. The company will take the actions necessary regarding the construction of the collection and treatment facilities to ensure compliance with Commission rule 20 CSR 4240-60.020(6) and will maintain records of all such actions taken.
- G. The gravity service sewer from the building to the pump station, the pressure service sewer from the pump unit to the customer's property line, and the pump station pit, floats, and electrical components shall be owned and maintained by the Customer. The Customer shall also install a check valve near the property line. The Customer shall notify the company of any malfunction in the operation of the sewer system serving Customer.
- H. A stopcock shall be placed on the service connection near the property line. Said stopcock shall include a provision for locking. The stopcock will be furnished, owned and maintained by the company. Sewer service may be disconnected by locking the stopcock in the closed position
- I. In all cases of discontinuance of sewer service pursuant to the Company's approved Rules, sewer service may be disconnected by the Company. Service shall not be resumed again except upon payment of all delinquent charges, plus any applicable approved service charge to cover the costs of effectuating resumption of service.
- J. The company will provide information for the customers' use in obtaining assistance on a 24/7 basis when a pump failure occurs.
- K. The company or authorized agent will perform the replacement of the repairable parts on the pump units, including maintaining the necessary inventory of such repairable parts and an inventory of at least one replacement pump for each 50 pumps, or fraction thereof, in service. The company shall not be liable for parts or labor necessary due to damage caused by misuse of the pump unit by the Customer or their agent.

* Indicates new rate or text

+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

- L. The Company shall not be liable for parts or labor necessary due to damage caused by misuse of the pump unit. The Customer and/or the owner of the premises wherein pump units are in operation shall be responsible for the care and safekeeping of the pump unit, including electrical service to the pump unit, to prevent freezing and overflow as well as damage due to flooding caused by the pump unit.
- M. In the event that the customer or the customer's agent shall damage the pump, pump station, station, control panel or any appurtenances thereto, the customer shall be responsible for the cost to repair any such damage, including replacement thereof, if necessary.

* Indicates new rate or text
+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

Rule 6 – Improper Waste or Excessive Use

- A. In the event that the Customer to be served proposes to discharge, or actually consistently discharges, an abnormally high volume or strength of waste, the Company may require:
1. The Customer to install a pretreatment facility, grease trap or other device on the premises, to prevent the exceeding of discharge limits, or other adverse impacts upon the Company's system. The installation of any such device as well as its operation, maintenance and cleaning as necessary but no less than annually and shall be the responsibility of the Customer, and subject to approval and inspection by the Company. At their discretion the Customer may provide a cleaning and maintenance invoice to the Company rather than inspection.
 2. The Customer to enter into a special contract with the Company for treatment of the Customer's discharge, that could require an enlargement of the Company's existing sewage treatment plant or the construction of a temporary sewage treatment plant, and/or the construction or reconstruction of sewer lines or pump facilities, in a form approved by the Missouri Public Service Commission with a rate applicable to the Customer to be included within this Schedule of Rates, Rules, and Regulations, that is fair and reasonable to both parties and so as not to constitute a burden upon the Company or the existing Customers of the Company.
- B. No Customer shall discharge or cause to be discharged any storm water, surface water, ground water, swimming pool water, roof runoff, sub-surface drainage, or cooling water into the collecting sewers.
- C. The Customer shall not tamper with, by-pass, remove, or willfully damage a water meter that is used for calculation of sewer bills, or allow any such action.
- D. The Customer shall not attempt to discharge sewage either by an unauthorized service connection or direct unauthorized connection to a service sewer.

* Indicates new rate or text

+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

- E. Customers will not be permitted to allow discharge in any way from premises other than the service address, nor to permit the use of their drains or connections to the service sewer for waste discharge by others, without permission from the Company.
- F. Except as may be provided in paragraph A.2., above, the Customer shall be required to take any action necessary to meet the following described wastewater limits before the wastewater is discharged into the collection sewer:
1. Maximum temperature of 150 degrees Fahrenheit.
 2. Maximum strength of four-hundred (400) parts per million Biological Oxygen Demand (B.O.D.).
 3. A maximum of one-hundred (100) parts per million, by weight, any fat, oil or grease.
 4. A maximum of twenty-five (25) parts per million, by weight, any soluble oils.
 5. No gasoline, benzene, naphtha, fuel oil, or other flammable or explosive liquid, solid or gas.
 6. No garbage that has not been properly shredded.
 7. No ashes, cinders, sand, mud, straw, shavings, metal, glass, rags, feathers, tar, plastics, wood or any other solid or viscous substance capable of causing obstruction to the flow in sewers or other interference with the proper operation of the sewer system.
 8. No wastewater having a pH less than 5.0 or greater than 9.0, or having any other corrosive property, capable of causing damage or hazard to structures, equipment or personnel of the Company.
 9. No wastewater containing heavy metals, toxic material, or Chemical Oxygen Demand (C.O.D.), in sufficient quantity to disrupt the operation of treatment facilities, or exceeding any limits which may be specified in a service contract for any such substance.

* Indicates new rate or text

+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

Rule 7 – Discontinuance of Service

A. The Company may discontinue service for any of the following reasons:

1. Non-payment of a delinquent account not in dispute; or
2. Failure to post a security deposit or guarantee acceptable to the utility; or
3. Unauthorized interference, diversion or use of the utility service situated or delivered on or about the Customer's premises; or
4. Misrepresentation of identity in obtaining utility service; or
5. Enclosing or obstructing any meter to make reading or repairs unreasonably difficult, or
6. Failure to comply with the terms and conditions of a settlement agreement.
7. Refusal after reasonable notice to grant access at reasonable times to equipment installed upon the premises of the Customer for the purpose of inspection, meter reading, maintenance or replacement; or
8. Violation of any of these Rules and Regulations on file with and approved by the Missouri Public Service Commission, for unauthorized resale of sewer service, or for any condition which adversely affects the safety of the Customer or other persons, or the integrity of the utility's sewer system; or
9. Non-payment of a sewer bill issued by the Company or by a sewer utility requesting discontinuance of water service by an agreement between the Company and such sewer utility. When water service is discontinued for non-payment of a sewer bill and that sewer bill is not issued by the Company, any service charges for turn on / off or disconnection/reconnection within these Rules and Regulations shall not apply, and notice

* Indicates new rate or text

+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

to the Customer shall be provided by rules and procedure applicable to the Customer's sewer service in lieu of notification required by these Rules and Regulations.

B. Discontinuance of service may be accomplished by, but not limited to, physical disconnection or turn-off of the Customer's service sewer from the Company's collecting sewer. Discontinuance of sewer service for non-payment of a sewer bill may be accomplished by physical disconnection or turn-off, or discontinuance by turn-off of water service by the Customer's water utility at the request of the Company. In such cases where discontinuance is accomplished by turn-off of water service:

1. If sewer billing is combined with water billing, Customers will be notified by the water utility by the terms of its rules normally practiced for discontinuance of water service; or
2. If sewer billing is not combined with water billing, Customers will be notified by the terms of paragraphs F. and H., below, and not by those of any water utility.

C. Reconnection of any Customer after discontinuance of service by authority of this rule will be made subject to payment of the cost of reconnection.

D. Where the owner of rental property is the Customer and has been notified of the intent of disconnection, the tenants shall be given the opportunity in a reasonable and timely manner to pay delinquent bills in lieu of disconnection of service.

E. None of the following shall constitute sufficient cause for the Company to discontinue service:

- * Indicates new rate or text
- + Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

1. The failure of the Customer to pay for merchandise, appliances, or service not subject to Commission jurisdiction as an integral part of the utility service provided by the Company; or
2. The failure of the Customer to pay for service received at a separate point of service, residence, or location. In the event of discontinuance or termination of service at a separate residential point of service, residence, or location in accordance with these rules, the Company may transfer and bill any unpaid balance to any other residential service account of the Customer and may discontinue service after twenty-one (21) days after rendition of the combined bill, for nonpayment, in accordance with this rule; or
3. The failure of the customer to pay for a different class of service received at the same or different location. The placing of more than one (1) service connection at the same location for the purpose of billing the usage of specific devices under operational rate schedules or provisions is not construed as a different class of service for the purpose of this rule; or
4. The failure to pay the bill of another customer, unless the customer whose service is sought to be discontinued received substantial benefit and use of the service billed to the other customer; or
5. The failure of a previous owner or occupant of the premises to pay an unpaid or delinquent bill except where the previous occupant remains an occupant of the living unit; or
6. The failure to pay a bill correcting a previous underbilling, whenever the customer claims an inability to pay the corrected amount, unless a utility has offered the customer a payment arrangement equal to the period of underbilling.

* Indicates new rate or text

+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

F. Unless discontinuance is accomplished by turn-off of water service and discontinuance notice is provided by the water utility, then at least thirty (30) days prior to discontinuance of service, the Company will mail a written notice to the Customer by certified mail, return receipt requested, with a copy of the notice sent to the Public Service Commission and a copy to the property owner if different than the Customer and if known by the Company. If the Company intends to discontinue service to a multi-tenant dwelling with occupants who are not customers, a notice shall also be conspicuously posted in the building ten (10) days prior to the proposed discontinuance, along with information pertaining to how one or more of the tenants may apply to become customers. Discontinuance shall occur within thirty (30) calendar days after the date given as the discontinuance date, shall occur between the hours of 9:00 a.m. and 4:00 p.m., and shall not occur on a day when the Company will not be available to reconnect service or on a day immediately preceding such a day. The thirty (30) day notice may be waived if there is any waste discharge that might be detrimental to the health and safety of the public, or cause damage to the sewer system. In the event of discontinuance of service without the thirty (30) day notice as above provided, the Customer and the Missouri Public Service Commission shall be notified immediately with a statement of the reasons for such discontinuance of service.

G. A discontinuance notice provided to a customer shall include:

1. The name and address of the Customer, the service address if different than the Customer's address; and
2. A statement of the reason for the proposed discontinuance of service and the cost for reconnection; and
3. How the customer may avoid the discontinuance; and
4. The possibility of a payment agreement if the claim is for a charge not in dispute and the Customer is unable to pay the charge in full at one time; and

* Indicates new rate or text

+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

5. A telephone number the Customer may call from the service location without incurring toll charges and the address and any available electronic contact information of the utility prominently displayed where the customer may make an inquiry.
- H. The Company shall make reasonable efforts to contact the Customer, at least twenty-four (24) hours prior to any discontinuance, regarding the reason(s) for discontinuance of service, and the resolution. If discontinuance of service would affect an occupant who is not the Company's Customer, or is not responsible for payment of the bill, then the Company shall make reasonable efforts to inform such occupant(s).
- I. The Company shall postpone the discontinuance if personnel will not be available to restore service the same day, or if personnel will not be available to restore service the following day. The Company also shall postpone discontinuance if a medical emergency exists on the premises, however the postponement may be limited to twenty-one (21) days, and the Company may require proof of a medical emergency.
- J. The Company shall have the right to enter the Customer's premises for purposes of discontinuance of service in compliance with these Rules and Regulations. Discontinuance of service will be made during reasonable hours. Company personnel shall identify themselves and announce the intention to discontinue service or leave a conspicuous notice of the discontinuance. The Company shall have the right to communicate with the owner of the Customer's Unit for purposes of gaining access to the property for discontinuance of service in accordance with the Missouri Public Service Commission's billing practices, but any extra costs for arranging such access shall not be charged to the Customer's account.
- K. The provisions of paragraphs I. and K., above, may be waived if safety of Company personnel while at the premises is a consideration.

* Indicates new rate or text
+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

- L. Discontinuance of service to a unit for any reason shall not prevent the Company from pursuing any lawful remedy by action at law or otherwise for the collection of monies due from the Customer.
- M. In case the Company discontinues its service for any violation of these Rules and Regulations, then any monies due the Company shall become immediately due and payable.
- N. The Company has the right to refuse or to discontinue service to any unit to protect itself against fraud or abuse.
- O. The Company shall deal with Customers and handle Customer accounts in accordance with the Missouri Public Service Commission's Utility Billing Practices.
- P. Applicable Turn-off and turn-on charges are specified in the Schedule of Service Charges.

* Indicates new rate or text
+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

Rule 8 – TERMINATION OF SERVICE

- A. Termination of service at the Customer's request may be accomplished at the expense of the Customer. If termination of service must be accomplished by physical disconnection, the Customer shall notify the Company of the date and time of the disconnection in writing at least five (5) days prior to the disconnection. If termination is accomplished by turn-off of water service, such notice shall be on or before the date of the water turn-off. Service may not be terminated for one unit of a multi-unit building if the building is served by one service sewer, unless accomplished by turnoff of water service to that unit. The method used for termination of service shall be determined by the Company.
- B. A Customer may request temporary turn-off of water service or sewer service by the Company for the Customer's own convenience; however, the Customer shall still be charged for service at the appropriate rate as specified in the Schedule of Rates during the time the service is turned off.

- * Indicates new rate or text
+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

Rule 9 – Interruptions in Service

- A. The Company reserves the right to limit sewer service in its collecting sewers at any time, in a reasonable and non-discriminatory manner, for the purpose of making repairs to the sewer system.
- B. Whenever service is limited for repairs, all Customers affected by such limitation will be notified in advance whenever it is practicable to do so. Every effort will be made to minimize limitation of service.
- C. No refunds of charges for sewer service will be made for limitations of service unless due to willful misconduct of the Company.

* Indicates new rate or text
+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

Rule 10 – Bills for Service

- A. The charges for sewer service shall be at the rates specified in the Schedule of Rates in these Rules and Regulations. Service charges for connection or disconnection are set forth in the Schedule of Service Charges.
- B. A Customer who has made application for, or who is or has been taking sewer service at one or more units connected to the collecting sewer, shall be held liable for payment of any applicable charges for service furnished to such units from the date of connection until the date requested by the Customer in writing for service to be terminated, or until service is discontinued by the Company.
- C. Bills for sewer service will be mailed or delivered to the Customer's last address as shown by the records of the Company, but failure to receive the bill will not relieve the Customer from the obligation to pay the same.
- D. Payments shall be made at the office of the Company or at a convenient location designated by the Company, by ordinary mail, or by electronic methods employed by the Company. Payment must be received by the close of business on the date due, unless the date due falls on a non-business day in which case payment must be received by the next business day.
- E. Neither the Company nor the Customer will be bound by bills rendered under mistake of fact as to the quantity of service rendered or as a result of clerical errors. Customers will be held responsible for charges based on service provided.
- F. Separate bills shall be rendered for each location at which sewer service is provided, even though one entity may be the Customer at such separate locations.
- G. The Company shall have the right to render bills monthly in advance, or on a monthly basis in arrears when the sewer charges are based on water usage. Bills

* Indicates new rate or text

+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

shall have the due date indicated on the bill. Bills will be rendered net, bearing the last date on which payment will then be considered delinquent. The period after which the payment is considered delinquent is a minimum of 21 days after rendition of the bill. Bills unpaid after the stated due date will be delinquent and the Company shall have the right to discontinue service in accordance with Rule 8. Delinquent bills may be subject to a late charge as provided in the Schedule of Service Charges. The Company shall not be required to restore or connect any new service for such delinquent Customers until the unpaid account due the Company under these Rules and Regulations has been paid in full or arrangements satisfactory to the Company have been made to pay said account.

- H. When bills are rendered for a period of less than a complete billing period due to the connection or termination of service, the billing shall be for the proportionate part of the monthly charge, or where water usage is the basis for the charge, at the appropriate rate for water used.
- I. Customers terminating after taking service for less than one month shall pay not less than the monthly minimum. The owner of the property served will be held responsible for ultimate payment of a bill. If the customer is a tenant of rental property, copies of all notices of violations of the rules, or of disconnection of service shall also be sent to the owner of the property if the owner is known to the Company.
- J. Unless sewer charges are billed in advance, the Company may require a security deposit or other guarantee as a condition of new service if the Customer:
1. Has a past-due bill which accrued within the last five (5) years and, at the time of the request for service, remains unpaid and not in dispute with a utility for the provision of the same type of service; or,
 2. Has, in an unauthorized manner, within the last five (5) years prior to applying for service, interfered with or diverted the service of a utility in the provision of the same type of service; or,

* Indicates new rate or text

+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

3. Is unable to establish a credit rating with the Company. Adequate credit rating for a residential Customer shall be established if the Customer:
 - a. Owns or is purchasing a home; or,
 - b. Is and has been regularly employed full time for at least one (1) year; or,
 - c. Has an adequate and regular source of income; or
 - d. Can provide credit references from a commercial credit source.
- K. Unless sewer charges are billed in advance, the Company may require a security deposit or other acceptable written guarantee of payment as a condition of continued or re-establishing service if service if:
 1. The water service of the Customer has been discontinued for non-payment of a delinquent account not in dispute; or,
 2. The Customer has interfered with, diverted or, in an unauthorized manner, used utility service delivered to the customer's premises; or,
 3. The Customer has failed to pay undisputed bills before the delinquency date for five (5) billing periods out of twelve (12) consecutive monthly billing periods. Prior to requiring a customer to post a deposit under this subsection, the utility shall send the customer a written notice explaining the utility's right to require a deposit or include such explanation with each written discontinuance notice.
- L. The amount of a security deposit shall not exceed utility charges applicable to one (1) billing period plus thirty (30) days, computed on estimated or actual annual usage.
- M. Interest shall be payable annually on all deposits, but shall not accrue after the utility has made reasonable effort to return the deposit. Interest will be paid at a per annum rate equal to the prime bank lending rate, as published in the *Wall*

* Indicates new rate or text

+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

Street Journal for the last business day of the preceding calendar year, plus one (1) percentage point. Interest may be credited to the Customer's account.

- N. After a Customer has paid proper and undisputed utility bills by the due dates, for a period not to exceed one (1) year, credit shall be established or re-established, and the deposit and any interest due shall be refunded. The utility may withhold full refund of the deposit pending resolution of a disputed matter.
- O. The utility shall give a receipt for deposits received, but shall also keep accurate records of deposits, including Customer name, service address, amounts, interest, attempts to refund and dates of every activity regarding the deposit.
- P. All billing matters shall be handled in accordance with the Missouri Public Service Commission's Rules and Regulations regarding Utility Billing Practices, 20 CSR 4240-13.

- * Indicates new rate or text
- + Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

Rule 11 – Extension Of Collecting Sewers

- A. Collecting sewers will be extended within the Company's certificated service area, at the applicant's cost, if service is requested by the applicant at a location where facilities do not exist (the "applicant" is sometimes referred to in this rule as the "original applicant"). The applicant shall enter into a contract with the Company. The applicant may choose to have the Company perform all work under the terms and conditions of Paragraph C, following, or have a private contractor perform the work under the terms and conditions of Paragraph D, following. For purposes of this rule, an extension could include, in addition to a collecting sewer, one or more pump station or treatment plant facilities, as necessary to provide the service.
- B. The pipe used in making extensions shall be of a type and size which will be reasonably adequate for the area to be served. Such determination as to size and type of pipe shall be left solely to the judgment of the Company. If the Company desires a pipe size, lift station, treatment plant, or any other facility larger than reasonably required to provide service to the applicant, the additional cost due to larger size shall be borne by the Company.
- C. The Company will extend collecting sewers for the applicant under the following terms and conditions:
1. Upon receipt of written application for service as provided in Rule 4, Applications for Service, the Company will provide the applicant an itemized estimate of the cost of the proposed extension. Said estimate shall include the cost of all labor and materials required, including reconstruction of existing facilities if necessary, and the direct costs associated with supervision, engineering, permits, and bookkeeping.
 2. The applicant shall enter into a contract with the Company for the installation of said extension and shall tender to the Company a contribution-in-aid-of-construction equal to the amount determined in Paragraph C (1) above, plus any appropriate fees as provided in the Schedule of Rates or the Schedule of Service Charges.

* Indicates new rate or text

+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

3. If, as a result of reasonably unforeseen circumstances, the actual cost of the extension exceeds the estimated cost of the extension, the applicant shall pay the additional cost.
- D. When the applicant elects to construct an extension, the Company will connect said extension to its existing collecting sewers under the following terms and conditions:
1. Applicant shall enter into a contract with the Company which provides that the applicant construct said collecting sewers and/or other facilities to meet the requirements of all governmental agencies and the Company's rules. Plans for the extension shall be submitted to the Company for approval prior to construction. Applicant's choice of construction contractor is subject to approval by the Company. Applicant shall contribute said facilities to the Company with a detailed accounting of the actual cost of construction and contribute to the Company the estimated reasonable cost of the Company's inspection.
 2. The Company, or its representative, shall have the right to inspect and test the extension prior to connecting it to the existing collecting sewers and acceptance of ownership.
 3. Connection of the extension to existing Company collecting sewers shall be made by, or under direct supervision of, the Company or its representative.
 4. The Company shall have the right to refuse ownership and responsibility for the sewer extension until applicant has met the contractual obligations as provided in Paragraph D (1).
- E. The cost to additional applicants connecting to the sewer contributed by the original applicant shall be as follows:
1. For a single-family residential applicant applying for service in a platted subdivision, the Company shall divide the actual cost of the extension, including income tax impact if any, by the number of lots abutting said

- * Indicates new rate or text
+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

extension to determine the per lot extension cost. When counting lots, corner lots which abut existing sewers shall be excluded.

2. For a single-family residential applicant requesting service to areas that are not platted in subdivision lots, the applicant's cost shall be equal to the total cost of the extension times 100 feet divided by the total length of the extension in feet.
3. For an industrial, commercial, or multi-family residential applicant, the cost will be equal to the amount calculated for a single-family residence in E (1) above or E (2) above, as appropriate, multiplied by a water usage factor. The water usage factor shall be determined by dividing the average monthly usage in gallons by 7,000 gallons but shall not be less than 1.

F. Refunds of contributions shall be made to the original applicant as follows:

1. Should the actual cost of an extension constructed by the Company under Paragraph C, or actual costs for inspection by the Company under Paragraph D, above, be less than the estimated cost, the Company shall refund the difference as soon as the actual cost has been ascertained.
2. During the first ten years after the extension is completed, the Company will refund to the original applicant who paid for the extension monies collected from additional applicants in accordance with Paragraph E above.
3. The sum of all refunds to the applicant shall not exceed the total contribution, including income tax and inspection costs associated with the extension, which the applicant has paid.
4. If two or more entities are considered an original applicant, the refund shall be distributed to each entity based upon the percentage of the actual extension cost contributed by each entity.

G. Any extension made under this rule shall be and remain the property of the Company in consideration of its perpetual upkeep and maintenance.

* Indicates new rate or text

+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address

Name of Utility: Timber Creek Sewer Company
Service Area: Certificated Areas in Missouri

Rules Governing Rendering of
Sewer Service

- H. The Company reserves the right to connect additional extensions to a collecting sewer contributed by the applicant. The connection of new customers to such additional extensions shall not entitle the applicant to any refund.

* Indicates new rate or text
+ Indicates change

DATE OF ISSUE July 31, 2026
Month Day Year

DATE EFFECTIVE August 30, 2026
Month Day Year

ISSUED BY Devin Sherry President
name of officer title

P.O. Box 511, Platte City, MO 64079
address